



Overview of the RISP Superconducting Linac

Dong-O Jeon The Rare Isotope Science Project Institute for Basic Science

ib^{S Institute} Concept of the Accelerator Complex RISP



SC Linac 200MeV/u for ²³⁸U, 600 MeV for $p \rightarrow$ IF driver, high power ISOL driver Cyclotron 70 MeV, 1mA for $p \rightarrow$ ISOL driver SC Linac ISOL post accelerator 18 MeV/u



RISP Site Plan







Bird's Eye View





ib^{S Institute for} Driver SC Linac Lattice Change

RISP

- Linac base frequency = 81.25 MHz
- Design to accelerate high intensity ion beams
- Flexile operation to meet the needs of various user groups



with NC doublets

with SC solenoids



quadrupole

SCL Design

1 QWR + 1 QD

3 HWR + 1 QD 4 HWR + 1 QD





beam box example (courtesy of SPIRAL2)



Quadrupole



beam box

Beam Box

486 mm

| SCL | Cavity structure | Frequency | β _g | Number of cavities | Output energy |
|------|---------------------|-----------|----------------|-----------------------|--------------------------------|
| SCL1 | QWR | 81.25 MHz | 0.047 | 24 | 2.7 MeV/u (U ⁺³³) |
| | HWR | 162.5 MHz | 0.12 | 131 | 18.6 MeV/u (U ⁺³³) |
| SCL2 | SSR | 325 MHz | 0.3 | 90 | 66 MeV/u (U ⁺⁷⁹) |
| | SSR | 325 MHz | 0.53 | 160 | 200 MeV/u (U ⁺⁷⁹) |

4 SSR + 1 QD

8 SSR + 1 QD

Driver SCL Lattice Change



NC quadrupole lattice option has the following merits:

- 1. Accurate alignment < 150 μ m of NC quadrupoles is feasible.
- 2. Beam quality control is straightforward and design is more adequate for high power beam operation.
- 3. Advantages in beam diagnostics and collimation through beam boxes.
- The linac cost seems to be in error range compared with the SC solenoid option. (← removal of costly SC solenoids)
- 5. Preliminary cryo-load comparison suggests that overall cryoload difference is small compared with the dynamic load.
- Linac length decrease : 97 m → 90 m for the SCL 1, compared with the previous design.





Beam Simulations in SCL1 $(\beta_1 + \beta_2)$







Phase advance in the SCL1 $(\beta_1 + \beta_2)$

Hyung Jin Kim

ISP







Beam Simulations in SCL2 $(\beta_3 + \beta_4)$







Phase Advance in SCL2 $(\beta_3 + \beta_4)$







Beam Simulations in SCL2 $(\beta_3 + \beta_4)$







Beam Simulations in SCL2 $(\beta_3 + \beta_4)$







Machine Imperfections

Hyung Jin Kim

| Parameters | SCRF | Warm | SC | Distribution | |
|-------------------|--------|------------|----------|--------------|--|
| | Cavity | Quadrupole | Solenoid | | |
| Displacement (mm) | ±1 | ±0.15 | ±0.5 | Uniform | |
| Rotation (mrad) | - | ±5 | - | Uniform | |
| Phase (deg) | ±1 | - | - | 3σ Gaussian | |
| Amplitude (%) | ±1 | - | - | 3σ Gaussian | |

• For actual accelerators, certain imperfections are unavoidable due to engineering/alignment imperfections.

¹ ^b ^{Institute for Basic Science} Machine imperfection simulations in β₁ section (baseline vs solenoid option) _{Hyung Jin Kim}



- The shade region represents the bounds of envelope, centroid and e mittance due to misalignment and field errors.
- Simulation shows that proposed baseline design improves beam quali ty significantly.



¹⁶ Cavity types are changed for high intensity, high power beam operation. Cavity geometry is optimized for all four types of the SC cavities.

1b^{S Institute for} Basic Science **Cavity Geometry Optimization** (dimensions are in cm)



The geometry of the quarter wave resonator is optimized.



Summary of optimized HWR





The geometry of the half wave resonator is optimized.



Summary of optimized SSR's





Cavity Parameters

Driver SCL load = 2.1 kW, ISOL SCL load = 0.33 kW

1SP

| Parameters | Unit | QWR | HWR | SSR 1 | SSR 2 |
|-------------------------------------|------|-------|-------|-------|-------|
| β_{g} | - | 0.047 | 0.12 | 0.30 | 0.53 |
| Resonant frequency | MHz | 81.25 | 162.5 | 325 | 325 |
| No of cavities | - | 24 | 131 | 90 | 160 |
| Aperture diameter | mm | 40 | 40 | 50 | 50 |
| QR _s | Ohm | 17.5 | 41.2 | 86.1 | 104.7 |
| R/Q | Ohm | 472.3 | 264.8 | 237.0 | 298.0 |
| V _{acc} | MV | 1.02 | 1.07 | 2.04 | 3.53 |
| E _{peak} | MV/m | 30 | 30 | 30 | 30 |
| B _{peak} | mT | 54.1 | 40.8 | 52.2 | 62.3 |
| E _{peak} /E _{acc} | | 5.08 | 6.2 | 4.06 | 4.15 |
| B _{peak} /E _{acc} | | 9.16 | 8.4 | 7.07 | 8.6 |
| Q _{calc} /10 ⁹ | - | 1.8 | 4.0 | 8.1 | 9.1 |
| Operating temperature | К | 2 | 2 | 2 | 2 |
| P ₀ | W | 2.7 | 2.0 | 4.8 | 8.4 |
| P _{beam} / emA (proton) | W | 854 | 925 | 1440 | 2770 |
| P _{beam} / emA (Uranium) | W | 113 | 134 | 524 | 926 |
| Beam current (Uranium) | ρμΑ | 9.5 | 9.5 | 8 | 8 |
| Average charge state (U) | - | 33.5 | 33.5 | 79 | 79 |

 $\mathbf{E}_{\mathrm{acc}} = \mathbf{V}_{\mathrm{acc}} / (\beta \lambda)$

Institute for Basic Science





ISOL post-accelerator

- For the ISOL SCL lattice, we are planning to share the same doublet lattice as the driver SCL to reduce cost and required R&D efforts.
- EBIS is considered rather than ECR IS, generating higher charge state beams.
- Design optimized for $A/q \le 8$.





Charge Stripper

- Previously carbon foil was considered as the charge stripper.
- We are designing the charge stripper section to accommodate liquid Li or He gas charge stripper.



Courtesy of FRIB



- Change from 180° chicane to 90° bend.
- Conforms better to the topography of the site.
- Shorter in length \rightarrow better control in longitudinal plane.
- Better in radiation activation control for the downstream section.
- Various Charge Strippers are under study.

16^{S Institute for} Basic Present Charge Stripping Section 90° bend

Hye-Jin Kim







Temp SRF Test Facility

- A contingency plan for the temporary Superconducting RF and Magnet Test Facility is being developed, considering a possible delay in procuring the site.
- Plan and cost estimation are developed.
- Cost is 2856 M KRW (= \$2.4 M) for SRF Facility and 1200 M KRW for Magnet Test Facility (20m x 20m)





Summary



- Base frequency of the SCL is determined.
- For the SCL, NC quadrupole lattice is adopted rather than the SC solenoid:
 - Better beam quality control
 - Beam diagnostics and collimation advantages
- Same design for the ISOL post-linac.
- Cavity types and geometric betas are determined.
- Cavity geometry is being optimized.





Summary

- Construction of the Superconducting RF Test Facility is under way.
- International Collaboration is an essential part for the success of the project.





Thanks for your attention!

